TECHNICAL SPECIFICATIONS

- All work performed under this Contract shall be in accordance with PennDOT specifications for Full Depth Pavement Replacement as set forth in Publication 447, Section MS-0370-0035 dated 2014 as well as the PennDOT MS-944 Form. Three (3) separate bid prices shall be provided for Jailhouse Alley, Meyers Alley and the Borough Parking lot adjacent to Jailhouse Alley.
- 2. Asphalt wearing course for each street and the parking lot must be applied no more than seven days after Full Depth Pavement Replacement base course and leveling course is applied for each street and the parking lot. Compacted paving depths for the alleys are 3.5"-25mm and 1.5" 9.5mm.

 Compacted paving depth for the parking lot is 3" 9.5mm.
- 3. Tack coat must be applied between leveling course and asphalt wearing course.
- 4. To control dust the Contractor shall furnish daily water application for Full Depth Pavement Replacement base course and leveling course until asphalt wearing course is applied.
- 5. The Contractor shall furnish surveying to ensure proper slope and curb reveal for Full Depth Pavement Replacement base course and leveling course before asphalt wearing course is applied.
- 6. The Borough Engineering Department shall furnish vertical and horizontal control points at the site. The Contractor shall be responsible for transferring the information from the control points to the work area. Borough Public Works Department shall be responsible for existing paving demolition and removal, subbase re-grading (inverted crown), and 2A stone base installation and compaction prior to paving.
- The Contractor shall furnish, erect, and maintain all necessary barricades and signing commensurate
 with standard safety practice applicable to on-street construction and in compliance with PennDOT
 Publication 213.
- 8. The Contractor shall be responsible for damage to private and public property adjacent to the work area and for damages to utilities within the work area.
- The Borough shall reserve the right to increase or decrease quantities of any bid item at the unit bid price submitted.
- 10. Manhole frames & covers provided by Borough if necessary. The Contractor is responsible for placement.
- 11. Disposal of excavated materials is the responsibility of the Contractor.
- 12. Disposal of millings is the responsibility of the Contractor

20 Contractor must contact

- 13. The Contractor shall furnish the Borough Manager with the name and telephone number of an individual who shall respond to and correct unsafe conditions within the limitations of the Contract during all non-working hours.
- 14. The Contractor shall be responsible for purchase, pickup, delivery, and placement of all materials, unless otherwise listed.
- 15. The Contractor, after starting, must continue working on project until completed unless otherwise agreed to in writing by the Borough.
- 16. Bidders are urged to arrange for an on-site inspection of this project prior to submitting a bid.
- The Contractor cannot close the street during construction except with permission of the Borough Manager.
- 18. Contractor shall provide and place Rough Road signs at each point of entry to the Work Zone.
- 19. All work shall be completed by

to coordinate locations on Borough-